BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18392/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Construction of RCC Drain and Covering slab near Raghavendra Mata at Venkatagiriyappa Layout in ward no 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N M SHIVAKUMAR		
				In Figures		In Words
1	72	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications etc complete as per specifications and directions of engineer in charge of the work	Cum	83.0	5976.00	Rupees Eighty Three Only
2	72	Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, etc complete as per specifications and directions of engineer in charge of the work	Cum	2174.0	156528.00	Rupees Two Thousand One Hundred Seventy Four Only
3	54	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4500.0	243000.00	Rupees Four Thousand Five Hundred Only
4	16	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5490.0	87840.00	Rupees Five Thousand Four Hundred Ninety Only
5	264	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	306.0	80784.00	Rupees Three Hundred Six Only
6	0.65	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	65000.0	42250.00	Rupees Sixty Five Thousand Only
7	55.8	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. etc complete as per specifications and directions of engineer in charge of the work	Cum	6300.0	351540.00	Rupees Six Thousand Three Hundred Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092
23/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N M SHIVAKUMAR		
				In Figures		In Words
8	360	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	97.0	34920.00	Rupees Ninety Seven Only
9	36	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., indluding cost of converyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification Concrete Pavement etc complete as per specifications and directions of engineer in charge of the work	Rmt	124.0	4464.00	Rupees One Hundred Twenty Four Only
10	192	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work	Sqm	642.0	123264.00	Rupees Six Hundred Forty Two Only
11	960	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded)etc complete as per specifications and directions of engineer in charge of the work	m	35.0	33600.00	Rupees Thirty Five Only
12	192	Providing two line dressing to granite stone slab / granite stone masonry as per specifications. etc complete as per specifications and directions of engineer in charge of the work	Sqm	888.0	170496.00	Rupees Eight Hundred Eighty Eight Only
13	72	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	106.0	7632.00	Rupees One Hundred Six Only
		Total			1342294.00	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

23/3/16

23/03